Dated 25th July 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 16th August 1918, for reconstructing the Fort anicut across Yagachi river. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred only (Rs. 200) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for reconstructing the Fort anicut across Yagachi river," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The contractor whose tender is accepted should make use of the following materials collected and paid for already.

Burnt stone slabs	213 s. ft.
Rough stone jelly	24 c. yds.
Burnt bricks	75,000
Concrete jelly	76½ c. yds.
Rough stones	50 c. yds.

Abstract of detailed quantities for reconstructing the Fort Anicut across Yagachi river, Chikmagalur Taluk.

No.	Items of work	Per	Quantity
1	Earthwork excavation	C. yd.	1,024
2	Excavation through soft rock	"	58
3	Baling water	L. S.	Rs.
4	Diverting the river water to irrigation channel by constructing ring bund ...	"	"
5	Concrete in surki mortar	C. ft.	3,288
6	Burnt brick in surki mortar	"	9,536
7	Burnt stone slabs, 6" dressed and fixed	S. ft.	775
8	Plastering with surki mortar	Sq.	25'28
9	Pointing with surki mortar	"	6'41
10	Rough stone work, new	C. yd.	384
11	Rough stone jelly backing	"	233
12	Turfing	Sq.	50'00
13	Unforeseen items	L. S.	Rs.

K. PONNAPPA,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

BANGALORE DISTRICT.

Notification.

It is hereby notified for the information of the public, that an old "Densmore Type-writer Machine" of this office, will be sold by public auction on the 20th August 1918 in the premises of the District Office Buildings.

2. The sale will commence at 1 P.M. and will be held by the Personal Assistant to the Deputy Commissioner, and subject to the confirmation by the Deputy Commissioner.

3. The highest or any bid may be rejected without giving any reason.

4. The accepted bidder should pay the amount immediately at the close of the sale, failing which the article will be resold at the expense and risk of such bidder, who will not be entitled to the profits if any.

5. The article may be inspected during office hours.

T. CHOKKANNA,